

**19<sup>th</sup> February 2018-02-19**

**TO: ALL BIDDERS**

**RE: ADDENDUM NO.1**

**ROADS MAINTENANCE WORKS FOR FY 2017/2018**

Pursuant to the above advertised tender, Kenya Wildlife Service's wishes to make the following amendment to the tender.

1. Change of scope of works in the BOQs; The BOQs for the tender numbers; **KWS/OT/R&F/22/2017-2018, KWS/OT/R&F/23/2017-2018 and KWS/OT/R&F/30/2017-2018** have been changed to read as here below; the budgets still remain the same as before
    - **BOQ for KWS/OT/R&F/22/2017-2018- Page 2 of this addendum**
    - **BOQ for KWS/OT/R&F/23/2017-2018- Page 3 of this addendum**
    - **BOQ for KWS/OT/R&F/30/2017-2018- Page 4, 5, & 6 of this addendum**
  - Note:** Discard the earlier versions of the Bill of Quantities for the above affected tenders
  2. Schedule for completed works is missing on tender No's **KWS/OT/R&F/21/2017-2018, KWS/OT/R&F/22/2017-2018, KWS/OT/R&F/23/2017-2018, KWS/OT/R&F/24/2017-2018 and KWS/OT/R&F/30/2017-2018.**
    - This has been provided in **page 7 of this addendum**. Insert this schedule immediately after schedule 11 in the mentioned tenders.
  3. The front page of "the tender document no **KWS/OT/R&F/30/2017-2018** is erroneously indicated as "**Open to All**"-this has been deleted to read **Open to Youth and Women**"
  4. This addendum shall be construed to form part of the tender document
- All other conditions remain

**TENDER NO KWS/OT/R&F/22/2017-2018**

**Routine Maintenance of Junction A109 (Kibwezi) -Chyulu Hills Road E1819**

<b>Item</b>	<b>Description of Work Item</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
04-50-004	<u>Light Bush Clearing</u> Cut grass by hand from shoulders, slopes, inlet ditches, side ditches including back slopes, turnouts and culvert outlets	M <sup>2</sup>	60,000		
08-60-008	Culvert cleaning	M	48		
08-70-006	Construction of scour checks (concrete)	No.	12		
08-60-016	Headwall repair-masonry	No.	6		
08-60-025	Culvert Installation 600mm Diameter with surround	No.	24		
10-50-003	Light Carriageway grading-	M <sup>2</sup>	60,000		
10-50-004	Light manual Carriageway reshaping; trim manually existing carriageway to camber, including slopes, ditches, without watering.	M <sup>2</sup>	120,000		
10-60-001	Provide gravel wearing course, excavate, free haul, spread and compact gravel equipment.	M <sup>3</sup>	4,500		
<b>A</b>	<b>SUB TOTAL</b>				
<b>B</b>	<b>Add 16% VAT</b>				
	<b>Total Carried Forward to Form of Tender(A+B)</b>				

<b>TENDER NO KWS/OT/R&amp;F/ 23 /2017-2018</b>					
<b>Routine Maintenance of Lali - Mifupa Ndovu-Ndia Ndasa - Ithumba-Kansiku (E903)</b>					
<b>Item</b>	<b>Description of Work Item</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
04-50-004	Light Bush Clearing	M <sup>2</sup>	25,000		
05-50-012	Rock fill to the drifts foundation	M <sup>3</sup>	68		
07-50-001	Excavation in soft for drifts	M <sup>3</sup>	200		
07-50-003	River training works	M <sup>3</sup>	1,100		
08-50-052	Ditch/ mitre catch water drain excavation	M <sup>3</sup>	720		
08-60-008	Culvert Cleaning- Fully Blocked - 600mm	MT	49		
10-50-003	<b><u>Carriageway grading -Light grading</u></b>				
	Trim with motor grader existing carriageway to camber, including slopes and ditches.	M <sup>2</sup>	650,000		
10-60-001	<b><u>Gravel Patching</u></b>				
	Prepare road formation, excavate from approved borrow pit ,haul ,spread water and compact gravel wearing course as per the specifications	M <sup>3</sup>	2,760		
17-60-001	<b><u>Class 15/20 blinding</u></b>				
	Provide place and compact concrete class 15/20 for blinding in drifts	M <sup>3</sup>	5		
17-60-002	<b><u>Class 20/25 for drift</u></b>				
	Provide place and compact concrete class 20/25 concrete for drifts	M <sup>3</sup>	75		
17-60-003	Vertical framework class F2 finish in drifts	M <sup>2</sup>	55		
17-60-005	Reinforcement 16mm and above for drift	Ton	2		
22-77-005	BRC -A252 for drift slab	M <sup>2</sup>	225		
A	<b>SUB TOTAL</b>				
B	<b>Add 16% VAT</b>				
	<b>Total Carried Forward to Form of Tender(A+B)</b>				









